Government of Nepal
Ministry of Urban Development
Department of Urban Development & Building Construction
Division Office Rupandehi

Bill of Quantity

Name of Project :- Interior Works of Arghakhachi City Hall Building
Project Site :- Sandhikharka ,Arghakhanchi

S.N	Description	Quantity	Unit	Rate Excluding VAT		Amount
				In Figure	In Words	
A	CIVIL WORKS					
1	FALSE CEILING					
	Supply and installation of 12 mm th. suspended gypsum board (Boral/ Elephant or equivalent) with 25 mm th. Glass wool (density 25) and underlay of a layer of plastic sheet, using GI channel, MS metal (25x4mm) hangers, screw on truss pipe in perfect line and level and necessary provision for light fittings, light boxes, where required, and installation of all complete as per drawing, specification and instruction of designer.	560.00	Sq.m			
2	WALL TREATMENT					
2.1	Supply and installation of 12 mm th. gypsum board (Boral/ Elephant or equivalent), with 25 mm th. Glass wool (density 16) covered with chicken net, using GI channel in perfect line and level and necessary provision for exhaust fan, where required, all complete as per drawing, specification and instruction of designer.	513.00	Sq.m			
2.2	Fabrication, supply and installation of 12mm th. Ply board (Surya/ Sagun or equivalent), with underframing of metal channel, 120x19 mm Shisam Wood panelling with Bevelled V-groove with good finish of chapra polish, on the upper portion of wall (4m height and 75mm projection), all complete as per design, specification and instruction of designer.	280.51	Sq.m			
2.3	Supply and installation of velore carpet (maroon shade) on lower portion of wall over gypsum board panelling, all complete as per design, specification and instruction of designer.	250.37	Sq.m			

Name of Bidder:-
Signature:-
Stamp:-
Date:-

डिभिजन प्रमुख

Name of Project :- Interior Works of Arghakhachi City Hall Building
Project Site :- Sandhikharka ,Arghakhanchi

S.N	Description	Quantity	Unit	Rate Excluding VAT		Amount
				In Figure	In Words	
3	COLUMN CLADDING					
	Fabrication, supply and installation of False Column using 12mm th. Plyboard over 4mm th. Natural teak plyboard (Surya/ Sagun or equivalent), finished with good quality chapra polish, with underframing of pine wood (50x75mm), all complete as per design, specification and instruction of designer.	70.14	Sq.m			
4	WOODEN SKIRTING					
	Fabrication, supply and installation of 19x120mm Sisham wood skirting, all round the wall, finished with good quality chapra polish, all complete as per design, specification and instruction of designer.	85.00	Rm			
5	STAGE ENTRANCE AND PANELLING ON STAGE					
5.1	Fabrication, supply and installation of Stage front entrance design using 12mm th. Ply board over 4mm th. natural teak (Surya/ Sagun or equivalent), finished with good quality chapra polish, with underframing of Pine Wood (68x70mm), all complete as per design, specification and instruction of designer.	45.58	Sq.m			
5.2	Fabrication, supply and installation of 120x19 mm Shisam Wood panelling with Bevelled V-groove with wooden moulding on edge, with good finish of chapra polish, on the raised part of stage, all complete as per design, specification and instruction of designer.	13.05	Sq.m			
6	FLOORING					
6.1	Supply and installation of Floor Carpet (Yeti or Equivalent) using necessary adhesive, on passage area over cement punning of approved shade by consultant ,all complete as per design, specification and instruction of designer.	252.90	Sq.m			
6.2	Supply and Installation of 7mm thk. Laminated wood (with interlocking joint) on floor over cement punning at stage area, all complete as per design, specification and instruction of designer.	105.00	Sq.m			

Name of Bidder:-
Signature:-
Stamp:-
Date:-

डिभिजन प्रमुख

Name of Project :- Interior Works of Arghakhachi City Hall Building
Project Site :- Sandhikharka ,Arghakhanchi

S.N	Description	Quantity	Unit	Rate Excluding VAT		Amount
				In Figure	In Words	
7	PAINT					
7.1	Supply and application of POP TEXTURE over Gypsum board on ceiling of any surface & shape, size & height applying required coats of primer inclusive of surface preparation by providing putty & sanding surface , all complete as per design, specification and instruction of designer.	510.40	Sq.m			
7.2	Application of two coats of approved shade of (Asain paints or equivalent) emulsion paint over POP TEXTURE over gypsum board of any surface & shape, size & height inclusive of surface preparation, all complete as per design.	510.40	Sq.m			
8	CURTAINS					
	Supply and installation of velvet curtains (export quality) as per design, specification and instruction of designer.	738.74	Sq.m			
9	VIDEO SCREEN					
	Fabrication, supply and installation of fixed screen, applying emulsion paint on white flex pasted on 12mm th. Plyboard fixed over underframing of 75x75mm metal square pipe (16 gauge) and 50x50mm metal square pipe (16 gauge) horizontally and vertically, all complete as per design, specification and instruction of designer.	69.75	Sq.m			
B	FURNITURE WORKS					
	CHAIR					
1	Supply and installation of ready made Auditorium chair foldable with steel frame,foam padding on seat and back,duly upholstered with rexin cloth by Godrej or Featherlite or equivalent, as per drawing specification and instruction of designer.	500	nos			

Name of Bidder:-
Signature:-
Stamp:-
Date:-

डिभिजन प्रमुख

Name of Project :- Interior Works of Arghakhachi City Hall Building
Project Site :- Sandhikharka ,Arghakhanchi

S.N	Description	Quantity	Unit	Rate Excluding VAT		Amount
				In Figure	In Words	
C	ELECTRICAL WORKS					
1	LIGHT POINT WIRING					
	Supply, delivery, conduit laying, wiring,testing and commissioning of the light points with 2 x 3/22 - for point wiring SWG and 2x 3/22 - for mains, PVC insulated copper wires through 12/16/25 mm HDP PVC pipe in existing wall, ceilings, false ceiling and floors including 18 SWG GI sheet box, circular boxes, junction box , ceiling rose and necessary connecting, fixing,insulating and jointing materials, chiselled of existing wall and floors and redoing the chiselld areas with cement and sand mortar as per the drawings, specifications, electricity rules and instructions all complete.(Cable Make: prakasha/ Janta /Trishakti or equivalent).	74	Pts			
2	LIGHT FIXTURES					
	Supply, delivery, installation, testing and commissioning of the following light fixtures with holders, chokes, ballast's, lamps, starters, dimmers, tube lights, lamps, transformers, control gears and accessories (whereever applicable) including necessary connecting, fixing and insulating materials as per the drawings, site conditions, specifications, electricity rules and instructions all complete. (Wipro or equivalent).					
2.1	1x 18 W CFL Recessed Type down Light Fixture	25	Set			
2.2	1x 18 W incandescent Recessed Type down Light Fixture	40	Set			
2.3	FDL 150 Flood Light 50 WATT	5	Set			

Name of Bidder:-
Signature:-
Stamp:-
Date:-

डिभिजन प्रमुख

Name of Project :- Interior Works of Arghakhachi City Hall Building
Project Site :- Sandhikharka ,Arghakhanchi

S.N	Description	Quantity	Unit	Rate Excluding VAT		Amount
				In Figure	In Words	
D	**SOUND SYSTEM**					
	Supply, delivery, installation, testing and commissioning of the following Sound system with all necessary accessories all works complete.					
1	**1000 Watt Amphere (AOTAL company or euivalent)**	**1**	Set			
2	**200 Watt wall mount speaker**	**6**	nos			
3	**Wireless microphone**	**1**	Set			
4	**Cable connector**	**12**	pcs			
5	**Installation charge**	**1**	job			

Name of Bidder:-
Signature:-
Stamp:-
Date:-

डिभिजन प्रमुख

Name of Project :- Interior Works of Arghakhachi City Hall Building
Project Site :- Sandhikharka ,Arghakhanchi

S.N	Description	Quantity	Unit	Rate Excluding VAT		Amount
				In Figure	In Words	
E	SEALING THE GAP BETWEEN WALL TOP AND CGI ROOF COVER					
1	First class Brickwork in sub-structure / super structure in (1:4) cement sand mortar with approved quality bricks in perfect line & level with necessary scaffolding including wetting the bricks, properly packing the joints & curing the works with all complete.	4.55	cum			
2	12.5 mm th cement sand plaster of mix (1:4) cement sand in brick wall including mixing mortar,applying required plaster in line level and plumb and finishing in regular even,smoothen surface including scafolding etc all complete as per specifications.	19.80	Sq.m			
3	Two coat Washable Distemper paint of approved colour and shade over one coat primer on plaster surface including cleaning and scaffolding all complete as per specification and instruction.	236	Sq.m			
4	Two coat Appex paint with Primer of approved colour and shade on plaster surface including cleaning ,wetting and scaffolding all complete as per specification and instruction.	236	Sq.m			
5	Provision of scaffolding for Brickwork and Painting all works complete as per site condition and works.	1	job			
F	EXPANSION JOINT COVERING WORK WITH 6 MM THICK MS PLATE FIXED ON ONE SIDE AND FREE SLIDING ON THE OTHER SIDE INCLUDING RED OXIDE PAINT AND ENAMEL PAINT ALL WORKS					
1	Expansion joint covering work with 6 mm thick MS plate fixed on one side and free sliding on the other side with red oxide paint all works complete as per specification and instruction of site engineer.	1712.55	kg			

Name of Bidder:-
Signature:-
Stamp:-
Date:-

डिभिजन प्रमुख

Name of Project :- Interior Works of Arghakhachi City Hall Building
Project Site :- Sandhikharka ,Arghakhanchi

S.N	Description	Quantity	Unit	Rate Excluding VAT		Amount
				In Figure	In Words	
2	**Supplying and application of Two coats of Enamel Painting on floor,column and stage expansion joint surface and shape,size,height with application of required coats of primer inclusive of surface preparation all complete as per the approved shade and colour of background as per specification and instruction of site incharge.**	**36.36**	Sq.m			
G	**PROVISIONAL SUM**					
i)	**Insurance.**		PS	**112,661.93**	**NRs. One Lakh Twelve Thousands Six Hundreds Sixty one and Paisa Ninety three only.**	**112,661.93**
ii)	**Preparation and submission of As Built Drawing of the Project.**		PS	**50,000.00**	**NRs. Fifty Thousands only.**	**50,000.00**
iii)	**Comission for Bank Guaranty.**		PS	**20,279.14**	**NRs. Twenty Thousands Two Hundreds Seventy nine and Paisa Fourteen only.**	**20,279.14**
				Sub Total		
				Vat @ 13%		
				Grand Total		

Note:-

A. The Rate quoted here under shall be inclusive of:-

1. Supplying the materials along with accessories to the site.
2. Fixing and erecting them in position as per general practices, specifications and instructions of site engineer.
3. Tests and maintenance up to the period, specified in the agreement.

B.The itemwise rate should be quoted without VAT.

Name of Bidder:-
Signature:-
Stamp:-
Date:-

डिभिजन प्रमुख